BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to Footpath and Roads in Ward No.07

Work Order No: EE (Project)/Ynk Zone/WO/ 22/2020-21 Dt:- 22/05/2020

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. Pruthviraj N	
				In figures	In words
1	388.80	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	116.00	Rupees One Hundred Sixteen Only
2	251.10	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	215.00	Rupees Two Hundred Fifteen Only
3	43.20	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge	Sqm	2450.00	Rupees Two Thousand Four Hundred Fifty Only
4	6.00	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	5675.00	Rupees Five Thousand Six Hundred Seventy Five Only
5	70.60	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6029.00	Rupees Six Thousand Twenty Nine Only
6	50.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge.	Nos	453.00	Rupees Four Hundred Fifty Three Only
7	108.00	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	88.00	Rupees Eighty Eight Only
8	34.02	Providing and fixing M.S.grill work for windows and ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM complete as per specifications.	Kgs	105.00	Rupees One Hundred Five Only
9		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone